

विद्युत वितरण खण्ड – प्रथम, उन्नाव
अतिअल्पकालीन निविदा सूचना

विद्युत वितरण खण्ड प्रथम उन्नाव के अन्तर्गत अधोलिखित कार्यों हेतु पंजीकृत, अनुभवी, आयकर एवं सेवाकर पंजीकृत ठेकेदारों से मुहरबन्द निविदाये अलग-अलग दो भागों में, प्रथम भाग में धरोहर धनराशि, आयकर/सेवाकर, पंजीयन प्रमाण पत्र एवं अनुभव प्रमाण पत्र आदि तथा द्वितीय भाग में निविदित करें, तकनीकी विवरण एवं अन्य नियम व शर्तें हों सम्मुख अंकित निविदा खुलने की तिथि को 15:00 बजे तक आमंत्रित की जाती है। निविदाये उसी दिन 16:00 बजे सार्वजनिक रूप से उपस्थित निविदादाताओं/उनके प्रतिनिधियों के समक्ष खोली जायेगी। प्रत्येक निविदा का मूल्य रु० 230.00 (समस्त करो सहित) निर्धारित है, जो अप्रतिदेय है।

क्र० सं०	निविदा सं०	कार्य का विवरण	निविदा खुलने की तिथि	धरोहर धनराशि रु०
1.	आकाश 37/विद्युत/2016-17	सोनू मिश्रा के घर के निकट गांधी नगर उन्नाव में एल० टी० लाइन के सुदृढीकरण का कार्य।	04.03.17	1000.00
2.	आकाश 38/विद्युत/2016-17	राजकीय पॉलिटेक्निक के निकट साईट नं०-2 औ० क्ष० उन्नाव में 63 के०वी०ए० क्षमता के नये वितरण परिवर्तक की स्थापना का कार्य।	04.03.17	500.00
3.	आकाश 39/विद्युत/2016-17	ग्राम विजयी खेड़ा ब्लाक सुमेरपुर उन्नाव में 25 के०वी०ए० क्षमता के नये वितरण परिवर्तक की स्थापना का कार्य।	04.03.17	1000.00
4.	आकाश 40/विद्युत/2016-17	तालिब सराय उन्नाव में स्थापित वितरण परिवर्तक की क्षमतावृद्धि (100 के०वी०ए० से 250 के०वी०ए०) का कार्य।	04.03.17	2000.00
5.	आकाश 41/विद्युत/2016-17	भार्गव स्कूल के निकट गांधी नगर उन्नाव में एच०टी० लाइन (3 फेज) के निर्माण का कार्य।	04.03.17	2500.00
6.	आकाश 42/विद्युत/2016-17	अवस्थी रेस्टोरेंट के निकट गांधी नगर उन्नाव में 250 के०वी०ए० क्षमता के वितरण परिवर्तक की स्थापना का कार्य।	04.03.17	2000.00

नियम व शर्तें :-

1. निविदा प्रपत्र खण्डीय कार्यालय से नकद निविदा जुल्क का भुगतान कर निविदा खुलने की तिथि से एक दिन पूर्व तक प्राप्त किया जा सकता है।
2. धरोहर धनराशि राट्रीयकृत बैंक द्वारा निर्गत बैंक गारन्टी, सी०डी०आर०/टी०डी०आर० अथवा एफ०डी०आर० जो अधिशाही अभियन्ता, विद्युत वितरण खण्ड-प्रथम, उन्नाव के पक्ष में बन्धक हो, के रूप में स्वीकार की जायेंगी।
3. निविदादाता निविदा प्रपत्र सीधे मध्योच्चल विद्युत वितरण निगम लि०, की वेबसाइट www.mvvn1.in से डाउनलोड कर सकते हैं जिसके लिए उन्हें निर्धारित निविदा मूल्य के समतुल्य बैंक ड्राफ्ट निविदा प्रपत्र के साथ जमा करना अनिवार्य होगा।
4. निविदादाता निविदा खुलने की निर्धारित तिथि से तीन दिन पूर्व तक विद्युत वितरण मंडल, उन्नाव, मुख्य अभियन्ता (वितरण) लखनऊ क्षेत्र, लखनऊ एवं प्रबन्ध निदेशक, म०वि०वि०नि०लि०, लखनऊ के कार्यालय में भी निविदाएं जमा कर सकते हैं।
5. निविदा खुलने की तिथि को अवकाश होने पर, निविदाये अगले कार्य दिवस पर खोली जायेंगी।
6. अधोहस्ताक्षरी के पास किसी एक या सभी निविदाओं को बिना कारण बतायें आंशिक या सम्पूर्ण रूप से स्वीकार करने या निरस्त करने का अधिकार सुरक्षित है।
7. सशर्त निविदाएं स्वीकार नहीं की जायेंगी।

अधिशाही अभियन्ता
विद्युत वितरण खण्ड – प्रथम
उन्नाव।

“राष्ट्रहित में बिजली बचायें, बल्ब की जगह एल०ई०डी० जलायें ”

Madhyanchal Vidyut Vitaran Nigam Limited

**Electricity Distribution
Division-I, Unnao.**

Tender No. 37/EDD-IU/2016-17

DATE OF OPENING:- 04.03.17

**Tender proforma
(to be filled by tenderer)
Important instruction of the tenderer**

Your tender shall not be considered if you fail to submit this proforma duly filled up replies should be completed without ambiguity and should be clearly written against each item.
(Attach extra sheets if the space-left not sufficient)

Sl. No	PARTICULARS				REPLIES	
1-	Specification No. against which your are tenderer					
2-	Receipt No. & Date vide which cost of tender specification fees deposited by you.					
3-	Name & Address of tenderer					
4-	Year since when the tenderer has started execution of work tender.					
5-	Do you agree to all the conditions of the tender specification and if not State the modifications clearly which you desire in general conditions from A/B. it may Please be noted that it shall be entirely at the desecration of the undersigned to accept or reject the modification proposed)					
6-	Account of earn money deposited with full details be submitted here					
7-	Please state clearly (Yes/No) if you would accept the order of modification in the form A/B are not acceptable to the corporation without imposing further conditions form your side.					
8-	Give two reference who can certify your financial status and capability to undertake execution of work/Supply. One of the reference should be of any scheduled Bank of India.					
9-	Name & Detailed address of Tenderer/ Proprietor/ Partners/Director be given.					
10	Statement of past/current experience in similar works in the following form:-					
Sl no	Name & address of ordering authority	Order/ Contract No. & Date	Particular of work executed	Quantum of work		Remarks
				Ordered	Completed	
1	2	3	4	5	6	7

11- What is the validity period of your tender.

12- Place & Date

Signature of Tenderer
With seal

MADHYANCHAL VIDYUT VITARAN NIGAM LIMITED
ELECTRICITY DISTRIBUTION DIVISION-I UNNAO
(TENDER No. 37/EDDIU/2016-17)

Date Of Opening: 04.03.17

Schedule of rates & Quantum Of Work for construction of L.T. Line Near House of Sonu Mishra at Gandhi Nagar Unnao under jurisdiction of S.D.O., EDSD-IIInd Unnao(under V.V.N. Year 2016-17)

Sl.No	Particulars of works	Unit	Qty.	Rate	Amount
1	Safe carriage of following materials from Electy. Store centre Unnao to work dump site alongwith loading, unloading & proper stacking distance within 20 Kms Appx.				
a	Pcc Poles 8.5 mtr Long	No.	4		
b	Other loose line materials including 3Ph. ABC single pole accessories, stay rod, earthing rod, Insulators, Distribution Box etc for L.T. Line.	Km length of Line	0.230		
2	Erection of PCC(single pole) between long spane including digging of pits, fitting of accessories alongwith cartage & dragging from dump store to pit site.	No.	4		
3	Grouting of pole As per RESPO Norms with Grouthing materials.	No.	2		
4	Earthing of poles & T/F with earthing rods as per RESSPO Norms	No.	2		
5	Digging of pits, fixing & nozzelling of stay wire and grouting of stay rods as per RESSPO norms alongwith cost of civil materials.	No.	3		
6	Laying, stringing & sagging of LT line by 3Ph. ABC (3x95+1x70+1x16) sq. mm on existing & New errected PCC Pole including all associated works with jointing, jumpering & binding on insulators as required.	Km length of Line	0.230		
7	Erection of PVC cable size 16 sq. mm at L.T. side of Existing T/F for connecting of L.T. Line.	mtr.	50		
8	Fixting of Distribution Box	No.	6		
9	Disconnected service Cable of Existing Consumers & Connected their service cable with Distribution Box as per Norms.	Job	1		
Total					
Taxes					

**Signature & seal of
Contractor**

**Executive Engineer
EDD-I Unnao**

MADHYANCHAL VIDYUT VITRAN NIGAM LIMITED

ELECTRICITY DISTRIBUTION DIVISION-I, UNNAO

Tender No. 37/ EDD-IU/2016-17 SPECIAL TERMS & CONDITIONS

- 1- The work shall be completed within **Three Month** from the date agreement/date of handing over material by the deptt.
- 2- Variation shall be admissible only with the approval of the committee.
- 3- The work shall be carried out in accordance with Indian Electricity Act and Rules & as per Construction Manual of U.P. Power Corporation Ltd. And RESSPO Schedule.
- 4- Any loss & damage shall be recovered from the contractor account.
- 5- No T & P shall be supplied by the department at any cost. The transportation arrangement for safe carriage of materials shall be made by the Contractor. at his own risk.
- 6- All general conditions of contract for execution of work will be governed as per from 'A' (General conditions for the supply of plant and the execution of work in the U.P. Power Corporation Ltd.)
- 7- The work shall be carried out under the direct supervision of Junior Engineer and Sub-Divisional Officer concerned.
- 8- Department will not be responsible for any accident, casualties and loss occurred at the time of execution of work. The contractor shall be fully responsible for the same.
- 9- The necessary permit for shutdown etc. will be given to the contractor by the representative of the department as and when required for completion of work in a planned way.
- 10- The 90% payment shall be made on receipt bill against the works completed subject to availability of fund and remaining 10% will be detained as security which will be paid after 6 month from the date of completion of full work.
- 11- The Income Tax and other taxes will be deducted from the bill, if and as applicable.
- 12- Penalty @ ½% per week subject to maximum of 10% of the total value of the contract will be levied and deducted if the work is not completed within the stipulated period.
- 13- Service Tax shall be payable @ prevailing norms.
- 14- EE Concerned shall make the final payment after completion of work subject to availability of funds.

Executive Engineer
Electricity Distribution Division-I
Unnao

Madhyanchal Vidyut Vitaran Nigam Limited

**Electricity Distribution
Division-I, Unnao.**

Tender No. 38/EDD-IU/2016-17

DATE OF OPENING:- 04.03.17

Tender proforma (to be filled by tenderer)

Your tender shall not be considered if you fail to submit this proforma duly filled up replies should be completed without ambiguity and should be clearly written against each item.

(Attach extra sheets if the space-left not sufficient)

Sl. No	PARTICULARS				REPLIES	
1-	Specification No. against which your are tenderer					
2-	Receipt No. & Date vide which cost of tender specification fees deposited by you.					
3-	Name & Address of tenderer					
4-	Year since when the tenderer has started execution of work tender.					
5-	Do you agree to all the conditions of the tender specification and if not State the modifications clearly which you desire in general conditions from A/B. it may Please be noted that it shall be entirely at the desecration of the undersigned to accept or reject the modification proposed)					
6-	Account of earn money deposited with full details be submitted here					
7-	Please state clearly (Yes/No) if you would accept the order of modification in the form A/B are not acceptable to the corporation without imposing further conditions form your side.					
8-	Give two reference who can certify your financial status and capability to undertake execution of work/Supply. One of the reference should be of any scheduled Bank of India.					
9-	Name & Detailed address of Tenderer/ Proprietor/ Partners/Director be given.					
10	Statement of past/current experience in similar works in the following form:-					
Sl no	Name & address of ordering authority	Order/ Contract No. & Date	Particular of work executed	Quantum of work		Remarks
				Ordered	Completed	
1	2	3	4	5	6	7

11- What is the validity period of your tender.

12- Place & Date

Signature of Tenderer
With seal

MADHYANCHAL VIDYUT VITARAN NIGAM LIMITED
ELECTRICITY DISTRIBUTION DIVISION-I UNNAO
(TENDER No. 38/EDDIU/2016-17)

Date Of Opening:04.03.17

Schedule of rates & Quantum Of Work for construction of H.T. Line with New 63 KVA T/F at Government Politecnic Near Site No. 2 Ind. Area Unnao under the area of SDO I-st(under V.V.N. 2016-17)

Sl.No	Particulars of works	Unit	Qty.	Rate	Amount
1	Safe carriage of following materials from Electy. Store centre Unnao to work dump site alongwith loading, unloading & proper stacking distance within 25 Kms Appx.				
a	PCC Pole 8.5 mtr Long	No.	2		
b	Other loose line materials including ACSR weasel conductor, double pole accessories, stay rod, earthing rod, Insulators.	Km length of Line	0.098		
c	Transformer 63 KVA	No.	1		
2	Erection of PCC double pole including digging of pits, fitting of accessories alongwith cartage & dragging from dump store to pit site.	No.	1		
3	Making of T-off arrangement including fabrication & fitting of accessories.	No.	1		
4	Grouting of pole As per RESPO Norms with Grouthing materials.	No.	2		
5	Earthing of poles & T/F with earthing rods as per RESSPO Norms	No.	2		
6	Digging of pits, fixing & nozzelling of stay wire and grouting of stay rods as per RESSPO norms alongwith cost of civil materials.	No.	3		
7	Laying, stringing & sagging of following type HT/LT line including all associated works with jointing, jumpering & binding on insulators as required.				
a	HT Line Three phase Three wire by ACSR weasel conductor.	Km length of Line	0.098		
8	Mounting of 63 KVA T/F on double Pole alongwith cartage and dragging from dump site to pit site	No.	1		
9	Erection of PVC Cable 3.5x70 sq. mm for connection of T/F with L.T. Line.	Job	1		
Total					
Taxes					

**Signature & seal of
Contractor**

**Executive Engineer
EDD-I Unnao**

MADHYANCHAL VIDYUT VITRAN NIGAM LIMITED

ELECTRICITY DISTRIBUTION DIVISION-I, UNNAO

Tender No. 38/ EDD-IU/2016-17

SPECIAL TERMS & CONDITIONS

- 1- The work shall be completed within **Three Month** from the date agreement/date of handing over material by the deptt.
- 2- Variation shall be admissible only with the approval of the committee.
- 3- The work shall be carried out in accordance with Indian Electricity Act and Rules & as per Construction Manual of U.P. Power Corporation Ltd. And RESSPO Schedule.
- 4- Any loss & damage shall be recovered from the contractor account.
- 5- No T & P shall be supplied by the department at any cost. The transportation arrangement for safe carriage of materials shall be made by the Contractor. at his own risk.
- 6- All general conditions of contract for execution of work will be governed as per from 'A' (General conditions for the supply of plant and the execution of work in the U.P. Power Corporation Ltd.)
- 7- The work shall be carried out under the direct supervision of Junior Engineer and Sub-Divisional Officer concerned.
- 8- Department will not be responsible for any accident, casualties and loss occurred at the time of execution of work. The contractor shall be fully responsible for the same.
- 9- The necessary permit for shutdown etc. will be given to the contractor by the representative of the department as and when required for completion of work in a planned way.
- 10- The 90% payment shall be made on receipt bill against the works completed subject to availability of fund and remaining 10% will be detained as security which will be paid after 6 month from the date of completion of full work.
- 11- The Income Tax and other taxes will be deducted from the bill, if and as applicable.
- 12- Penalty @ ½% per week subject to maximum of 10% of the total value of the contract will be levied and deducted if the work is not completed within the stipulated period.
- 13- Service Tax shall be payable @ prevailing norms.
- 14- EE Concerned shall make the final payment after completion of work subject to availability of funds.

Executive Engineer
Electricity Distribution Division-I
Unnao

Madhyanchal Vidyut Vitaran Nigam Limited

**Electricity Distribution
Division-I, Unnao.**

Tender No. 39/EDD-IU/2016-17

DATE OF OPENING:-04.03.17

**Tender proforma
(to be filled by tenderer)
Important instruction of the tenderer**

Your tender shall not be considered if you fail to submit this proforma duly filled up replies should be completed without ambiguity and should be clearly written against each item.
(Attach extra sheets if the space-left not sufficient)

Sl. No	PARTICULARS				REPLIES	
1-	Specification No. against which your are tenderer					
2-	Receipt No. & Date vide which cost of tender specification fees deposited by you.					
3-	Name & Address of tenderer					
4-	Year since when the tenderer has started execution of work tender.					
5-	Do you agree to all the conditions of the tender specification and if not State the modifications clearly which you desire in general conditions from A/B. it may Please be noted that it shall be entirely at the desecration of the undersigned to accept or reject the modification proposed)					
6-	Account of earn money deposited with full details be submitted here					
7-	Please state clearly (Yes/No) if you would accept the order of modification in the form A/B are not acceptable to the corporation without imposing further conditions form your side.					
8-	Give two reference who can certify your financial status and capability to undertake execution of work/Supply. One of the reference should be of any scheduled Bank of India.					
9-	Name & Detailed address of Tenderer/ Proprietor/ Partners/Director be given.					
10	Statement of past/current experience in similar works in the following form:-					
Sl no	Name & address of ordering authority	Order/ Contract No. & Date	Particular of work executed	Quantum of work		Remarks
				Ordered	Completed	
1	2	3	4	5	6	7

11- What is the validity period of your tender.

12- Place & Date

Signature of Tenderer
With seal

MADHYANCHAL VIDYUT VITARAN NIGAM LIMITED
ELECTRICITY DISTRIBUTION DIVISION-I UNNAO
(TENDER No. 39/EDDIU/2016-17)

Date Of Opening:04.03.17

Schedule of rates & Quantum Of Work for Construction of New 25 KVA S/S at Village Vijai Khera Block Sumerpur Unnao under the area of S.D.O. Illrd Unnao (under B.P. Year 2016-17).

Sl.No	Particulars of works	Unit	Qty.	Rate	Amount
1	Safe carriage of following materials from Electy. Store centre Unnao to work dump site alongwith loading, unloading & proper stacking distance within 0-70 Kms Appx.				
a	PCC Pole 8.5 mtr Long	No.	11		
b	Other loose line materials including ACSR weasel conductor, AB conductor, single & double pole accessories, stay rod, earthing rod, Insulators and X-arm etc for Following Lines.				
(i)	H.T. Line 3-Ph Three wire with ACSR Weasel Conductor.	Km length of Line	0.900		
(ii)	L.T. Line with 3-Ph Three wire with AB Conductor.	Km length of Line	0.150		
(iii)	Transformer 25 KVA	No.	1		
2	Erection of PCC single pole including digging of pits, fitting of accessories alongwith cartage & dragging from dump store to pit site.	No.	9		
3	Erection of PCC double pole including digging of pits, fitting of accessories alongwith cartage & dragging from dump store to pit site.	No.	1		
4	Making of T-off arrangement including fabrication & fitting of accessories.	No.	1		
5	Grouting of pole As per RESPO Norms with Grouthing materials.	No.	7		
6	Earthing of poles & T/F with earthing rods as per RESSPO Norms	No.	7		
7	Digging of pits, fixing & nozzelling of stay wire and grouting of stay rods as per RESSPO norms alongwith cost of civil materials.	No.	5		
8	Laying, stringing & sagging of following type HT/LT line including all associated works with jointing, jumpering & binding on insulators as required.				
a	HT Line Three phase Three wire by ACSR weasel conductor.	Km length of Line	0.900		
b	LT Line Three phase by AB Conductor 3-Ph.(3x50+1x35+ 1x16) sq. mm	Km length of Line	0.150		
9	Mounting of 25 KVA T/F on double Pole alongwith cartage and dragging from dump site to pit site		1		
Total					
Taxes					

**Signature & seal of
Contractor**

**Executive Engineer
EDD-I Unnao**

MADHYANCHAL VIDYUT VITRAN NIGAM LIMITED

ELECTRICITY DISTRIBUTION DIVISION-I, UNNAO

Tender No. 39/ EDD-IU/2016-17

SPECIAL TERMS & CONDITIONS

- 1- The work shall be completed within **Three Month** from the date agreement/date of handing over material by the deptt.
- 2- Variation shall be admissible only with the approval of the committee.
- 3- The work shall be carried out in accordance with Indian Electricity Act and Rules & as per Construction Manual of U.P. Power Corporation Ltd. And RESSPO Schedule.
- 4- Any loss & damage shall be recovered from the contractor account.
- 5- No T & P shall be supplied by the department at any cost. The transportation arrangement for safe carriage of materials shall be made by the Contractor. at his own risk.
- 6- All general conditions of contract for execution of work will be governed as per from 'A' (General conditions for the supply of plant and the execution of work in the U.P. Power Corporation Ltd.)
- 7- The work shall be carried out under the direct supervision of Junior Engineer and Sub-Divisional Officer concerned.
- 8- Department will not be responsible for any accident, casualties and loss occurred at the time of execution of work. The contractor shall be fully responsible for the same.
- 9- The necessary permit for shutdown etc. will be given to the contractor by the representative of the department as and when required for completion of work in a planned way.
- 10- The 90% payment shall be made on receipt bill against the works completed subject to availability of fund and remaining 10% will be detained as security which will be paid after 6 month from the date of completion of full work.
- 11- The Income Tax and other taxes will be deducted from the bill, if and as applicable.
- 12- Penalty @ ½% per week subject to maximum of 10% of the total value of the contract will be levied and deducted if the work is not completed within the stipulated period.
- 13- Service Tax shall be payable @ prevailing norms.
- 14- EE Concerned shall make the final payment after completion of work subject to availability of funds.

Executive Engineer
Electricity Distribution Division-I
Unnao

Madhyanchal Vidyut Vitaran Nigam Limited

**Electricity Distribution
Division-I, Unnao.**

Tender No. 40/EDD-IU/2016-17

DATE OF OPENING:- 04.03.17

**Tender proforma
(to be filled by tenderer)
Important instruction of the tenderer**

Your tender shall not be considered if you fail to submit this proforma duly filled up replies should be completed without ambiguity and should be clearly written against each item.
(Attach extra sheets if the space-left not sufficient)

Sl. No	PARTICULARS				REPLIES	
1-	Specification No. against which your are tenderer					
2-	Receipt No. & Date vide which cost of tender specification fees deposited by you.					
3-	Name & Address of tenderer					
4-	Year since when the tenderer has started execution of work tender.					
5-	Do you agree to all the conditions of the tender specification and if not State the modifications clearly which you desire in general conditions from A/B. it may Please be noted that it shall be entirely at the desecration of the undersigned to accept or reject the modification proposed)					
6-	Account of earn money deposited with full details be submitted here					
7-	Please state clearly (Yes/No) if you would accept the order of modification in the form A/B are not acceptable to the corporation without imposing further conditions form your side.					
8-	Give two reference who can certify your financial status and capability to undertake execution of work/Supply. One of the reference should be of any scheduled Bank of India.					
9-	Name & Detailed address of Tenderer/ Proprietor/ Partners/Director be given.					
10	Statement of past/current experience in similar works in the following form:-					
Sl no	Name & address of ordering authority	Order/ Contract No. & Date	Particular of work executed	Quantum of work		Remarks
				Ordered	Completed	
1	2	3	4	5	6	7

11- What is the validity period of your tender.

12- Place & Date

Signature of Tenderer
With seal

MADHYANCHAL VIDYUT VITARAN NIGAM LIMITED
ELECTRICITY DISTRIBUTION DIVISION-I UNNAO
(TENDER No. 40/EDDIU/2016-17)

Date Of Opening:04.03.17

Schedule of rates & Quantum Of Work for increasng capacity of T/F 100 KVA to 250 KVA at vill. Talib Sarayan Unnao under the area of S.D.O. IInd Unnao (under V.V.N. Year 2016-17)

Sl.No	Particulars of works	Unit	Qty.	Rate	Amount
1	Safe carriage of following materials from Electy. Store centre Unnao to work dump site alongwith loading, unloading & proper stacking distance within 0-25 Kms Appx.				
a	Transformer 250 KVA	No.	1		
b	L.T. PVC Cable 1x400 sq. mm 40 mtr Aluminium Lugs Crimping type for 250 KVA T/F 04 No.	Job	1		
2	Dismantelling of 100 KVA T/F on existing D/pole alongwith cartage from work site to ESC Unnao.	No.	1		
3	Construction of Transformer plinth of size 2x2x1.5 meter with the help of first class brick and sand corse in the ratio 1:4 Cement and sand corse filling the structure completely as per norms with RCC top 1:2:2 cements sand corse and Stone Joint with MS bar and MS channel for resting transformer while 125x65x200 mm ² and plaster.	No.	1		
4	Fabrication and errection of wire mesh fencing 2 mtr. height including grouting of fabricated MS angle 50x50x6 mm ² painting of fencing and support with all material as per specification arround 11/0.4 KVA S/S the fencing shall be made of 50x25 mm ² 10 SWG rectangular type wire mesh which shall be fixed on panel made on 50x50x6 mm ² MS angle Iron. The Wire mesh on panel will be supported by 25x3 mtr. MS Flat and all the diagonally and the ms Angle Iron Horigently at the enter of the panel will be jointeted by N&B and nuts of approximately size with each other on the main support on the corner.	No.	1		
5	Mounting of 250 KVA T/f on plinth after construction of transformer plinth & Erection of PVC Cable 1x400 sq. mm with All. Lugs suitable for 250 KVA T/F & connection with T/F & L.T. Line.	No.	1		
Total					
Taxes					

**Signature & seal of
Contractor**

**Executive Engineer
EDD-I Unnao**

MADHYANCHAL VIDYUT VITRAN NIGAM LIMITED

ELECTRICITY DISTRIBUTION DIVISION-I, UNNAO

Tender No. 40/ EDD-IU/2016-17

SPECIAL TERMS & CONDITIONS

- 1- The work shall be completed within **Three Month** from the date agreement/date of handing over material by the deptt.
- 2- Variation shall be admissible only with the approval of the committee.
- 3- The work shall be carried out in accordance with Indian Electricity Act and Rules & as per Construction Manual of U.P. Power Corporation Ltd. And RESSPO Schedule.
- 4- Any loss & damage shall be recovered from the contractor account.
- 5- No T & P shall be supplied by the department at any cost. The transportation arrangement for safe carriage of materials shall be made by the Contractor. at his own risk.
- 6- All general conditions of contract for execution of work will be governed as per from 'A' (General conditions for the supply of plant and the execution of work in the U.P. Power Corporation Ltd.)
- 7- The work shall be carried out under the direct supervision of Junior Engineer and Sub-Divisional Officer concerned.
- 8- Department will not be responsible for any accident, casualties and loss occurred at the time of execution of work. The contractor shall be fully responsible for the same.
- 9- The necessary permit for shutdown etc. will be given to the contractor by the representative of the department as and when required for completion of work in a planned way.
- 10- The 90% payment shall be made on receipt bill against the works completed subject to availability of fund and remaining 10% will be detained as security which will be paid after 6 month from the date of completion of full work.
- 11- The Income Tax and other taxes will be deducted from the bill, if and as applicable.
- 12- Penalty @ ½% per week subject to maximum of 10% of the total value of the contract will be levied and deducted if the work is not completed within the stipulated period.
- 13- Service Tax shall be payable @ prevailing norms.
- 14- EE Concerned shall make the final payment after completion of work subject to availability of funds.

Executive Engineer
Electricity Distribution Division-I
Unnao

Madhyanchal Vidyut Vitaran Nigam Limited

**Electricity Distribution
Division-I, Unnao.**

Tender No. 41/EDD-IU/2016-17

DATE OF OPENING:- 04.03.17

**Tender proforma
(to be filled by tenderer)
Important instruction of the tenderer**

Your tender shall not be considered if you fail to submit this proforma duly filled up replies should be completed without ambiguity and should be clearly written against each item.
(Attach extra sheets if the space-left not sufficient)

Sl. No	PARTICULARS				REPLIES	
1-	Specification No. against which your are tenderer					
2-	Receipt No. & Date vide which cost of tender specification fees deposited by you.					
3-	Name & Address of tenderer					
4-	Year since when the tenderer has started execution of work tender.					
5-	Do you agree to all the conditions of the tender specification and if not State the modifications clearly which you desire in general conditions from A/B. it may Please be noted that it shall be entirely at the desecration of the undersigned to accept or reject the modification proposed)					
6-	Account of earn money deposited with full details be submitted here					
7-	Please state clearly (Yes/No) if you would accept the order of modification in the form A/B are not acceptable to the corporation without imposing further conditions form your side.					
8-	Give two reference who can certify your financial status and capability to undertake execution of work/Supply. One of the reference should be of any scheduled Bank of India.					
9-	Name & Detailed address of Tenderer/ Proprietor/ Partners/Director be given.					
10	Statement of past/current experience in similar works in the following form:-					
Sl no	Name & address of ordering authority	Order/ Contract No. & Date	Particular of work executed	Quantum of work		Remarks
				Ordered	Completed	
1	2	3	4	5	6	7

11- What is the validity period of your tender.

12- Place & Date

Signature of Tenderer
With seal

MADHYANCHAL VIDYUT VITARAN NIGAM LIMITED
ELECTRICITY DISTRIBUTION DIVISION-I UNNAO
(TENDER No. 41/EDDIU/2016-17)

Date Of Opening: 04.03.17

Schedule of rates & Quantum Of Work for construction of New L.T. Line Near Bhargao School At Gandhi Nagar Unnao under the area of S.D.O. IInd Unnao(under V.V.N. Year 2016-17)

Sl.No	Particulars of works	Unit	Qty.	Rate	Amount
1	Safe carriage of following materials from Electy. Store centre Unnao to work dump site alongwith loading, unloading & proper stacking distance within 20 Kms Appx.				
a	P.C.C. Pole 8.5 mtr Long	No.	10		
b	Other loose line materials including AB conductor, single pole accessories, stay rod, earthing rod, Insulators Distribution Box etc.	Km length of Line	0.462		
2	Erection of PCC (single pole) including digging of pits, fitting of accessories alongwith cartage & dragging from dump store to pit site.	No.	10		
3	Grouting of pole As per RESPO Norms with Grouthing materials.	No.	2		
4	Digging of pits, fixing & nozzelling of stay wire and grouting of stay rods as per RESSPO norms alongwith cost of civil materials.	No.	5		
5	Earthing of poles & T/F with earthing rods as per RESSPO Norms	No.	2		
6	Laying, stringing & sagging of LT line by 3x120+1x95+1x16 sq.mm 3-Ph AB Conductor including all associated works with jointing, jumpering & binding on insulators as required.	Km length of Line	0.462		
7	Erection of PVC Cable 16 sq. mm single core for connection of New L.T. Line with T/F at L.T. Side	Job	1		
8	Fixting of Distribution Box	No.			
9	Disconnected service Cable of Existing Consumers & Connected their service cable with Distribution Box as per Norms.	Job	1		
Total					
Taxes					

**Signature & seal of
Contractor**

**Executive Engineer
EDD-I Unnao**

MADHYANCHAL VIDYUT VITRAN NIGAM LIMITED

ELECTRICITY DISTRIBUTION DIVISION-I, UNNAO

Tender No. 41/ EDD-IU/2016-17

SPECIAL TERMS & CONDITIONS

- 1- The work shall be completed within **Three Month** from the date agreement/date of handing over material by the deptt.
- 2- Variation shall be admissible only with the approval of the committee.
- 3- The work shall be carried out in accordance with Indian Electricity Act and Rules & as per Construction Manual of U.P. Power Corporation Ltd. And RESSPO Schedule.
- 4- Any loss & damage shall be recovered from the contractor account.
- 5- No T & P shall be supplied by the department at any cost. The transportation arrangement for safe carriage of materials shall be made by the Contractor. at his own risk.
- 6- All general conditions of contract for execution of work will be governed as per from 'A' (General conditions for the supply of plant and the execution of work in the U.P. Power Corporation Ltd.)
- 7- The work shall be carried out under the direct supervision of Junior Engineer and Sub-Divisional Officer concerned.
- 8- Department will not be responsible for any accident, casualties and loss occurred at the time of execution of work. The contractor shall be fully responsible for the same.
- 9- The necessary permit for shutdown etc. will be given to the contractor by the representative of the department as and when required for completion of work in a planned way.
- 10- The 90% payment shall be made on receipt bill against the works completed subject to availability of fund and remaining 10% will be detained as security which will be paid after 6 month from the date of completion of full work.
- 11- The Income Tax and other taxes will be deducted from the bill, if and as applicable.
- 12- Penalty @ ½% per week subject to maximum of 10% of the total value of the contract will be levied and deducted if the work is not completed within the stipulated period.
- 13- Service Tax shall be payable @ prevailing norms.
- 14- EE Concerned shall make the final payment after completion of work subject to availability of funds.

Executive Engineer
Electricity Distribution Division-I
Unnao

Madhyanchal Vidyut Vitaran Nigam Limited

**Electricity Distribution
Division-I, Unnao.**

Tender No. 42/EDD-IU/2016-17

DATE OF OPENING:- 04.03.17

**Tender proforma
(to be filled by tenderer)
Important instruction of the tenderer**

Your tender shall not be considered if you fail to submit this proforma duly filled up replies should be completed without ambiguity and should be clearly written against each item.
(Attach extra sheets if the space-left not sufficient)

Sl. No	PARTICULARS				REPLIES	
1-	Specification No. against which your are tenderer					
2-	Receipt No. & Date vide which cost of tender specification fees deposited by you.					
3-	Name & Address of tenderer					
4-	Year since when the tenderer has started execution of work tender.					
5-	Do you agree to all the conditions of the tender specification and if not State the modifications clearly which you desire in general conditions from A/B. it may Please be noted that it shall be entirely at the desecration of the undersigned to accept or reject the modification proposed)					
6-	Account of earn money deposited with full details be submitted here					
7-	Please state clearly (Yes/No) if you would accept the order of modification in the form A/B are not acceptable to the corporation without imposing further conditions form your side.					
8-	Give two reference who can certify your financial status and capability to undertake execution of work/Supply. One of the reference should be of any scheduled Bank of India.					
9-	Name & Detailed address of Tenderer/ Proprietor/ Partners/Director be given.					
10	Statement of past/current experience in similar works in the following form:-					
Sl no	Name & address of ordering authority	Order/ Contract No. & Date	Particular of work executed	Quantum of work		Remarks
				Ordered	Completed	
1	2	3	4	5	6	7

11- What is the validity period of your tender.

12- Place & Date

Signature of Tenderer
With seal

MADHYANCHAL VIDYUT VITARAN NIGAM LIMITED
ELECTRICITY DISTRIBUTION DIVISION-I UNNAO
(TENDER No. 42/EDDIU/2016-17)

Date Of Opening: 04.03.17

Schedule of rates & Quantum Of Work for Construction of New 250 KVA S/S Near Awasthi Restorent at Gandhi Nagar Unnao under the area of S.D.O. IInd Unnao (under V.V.N, Year 2016-17).

Sl.No	Particulars of works	Unit	Qty.	Rate	Amount
1	Safe carriage of following materials from Electy. Store centre Unnao to work dump site alongwith loading, unloading & proper stacking distance within 25 Kms Appx.				
a	S.T. Pole 11 mtr Long	No.	2		
b	Other loose line materials for Three phase 3 Wire H.T. Line including ACSR weasel conductor, double pole accessories, stay rod, earthing rod, Insulators etc.	Km length of Line	0.100		
c	Transformer 250 KVA	No.	1		
2	Erection of ST (double pole) including digging of pits, fitting of accessories alongwith cartage & dragging from dump store to pit site.	No.	1		
3	Making of T-off arrangement including fabrication & fitting of accessories.	No.	1		
4	Grouting of pole As per RESPO Norms with Grouthing materials.	No.	2		
5	Earthing of poles & T/F with earthing rods as per RESSPO Norms	No.	2		
6	Digging of pits, fixing & nozzelling of stay wire and grouting of stay rods as per RESSPO norms alongwith cost of civil materials.	No.	4		
7	Laying, stringing & sagging of following type HT/LT line including all associated works with jointing, jumpering & binding on insulators as required.				
a	HT Line Three phase Three wire by ACSR weasel conductor.	Km length of Line	0.100		
8	Construction of Transformer plinth of size 2x2x1.5 meter with the help of first class brick and sand corse in the ratio 1:4 Cement and sand corse filling the structure completely as per norms with RCC top 1:2:2 cements sand corse and Stone Joint with MS bar and MS channel for resting transformer while 125x65x200 mm2 and plaster.	No.	1		
9	Fabrication and errection of wire mesh fencing 2 mtr. height including grouting of fabricated MS angle 50x50x6 mm2 painting of fencing and support with all material as per specification arround 11/0.4 KVA S/S the fencing shall be made of 50x25 mm2 10 SWG rectangular type wire mesh which shall be fixed on panel made on 50x50x6 mm2 MS angle Iron. The Wire mesh on panel will be supported by 25x3 mtr. MS Flat and all the diagonally and the ms Angle Iron Horigently at the enter of the panel will be jointeted by N&B and nuts of approximately size with each other on the main support on the corner.	No.	1		

10	Mounting of T/F on plinth & construction of transformer plinth & erection of PVC Cable size 3.5x400 sq mm with All. Lugs suitable for 250 KVA T/F & connected it with T/F & L.T. Lines.	No.	1		
Total					
Taxes					

**Signature & seal of
Contractor**

**Executive Engineer
EDD-I Unnao**

MADHYANCHAL VIDYUT VITRAN NIGAM LIMITED

ELECTRICITY DISTRIBUTION DIVISION-I, UNNAO

Tender No. 42/ EDD-IU/2016-17

SPECIAL TERMS & CONDITIONS

- 1- The work shall be completed within **Three Month** from the date agreement/date of handing over material by the deptt.
- 2- Variation shall be admissible only with the approval of the committee.
- 3- The work shall be carried out in accordance with Indian Electricity Act and Rules & as per Construction Manual of U.P. Power Corporation Ltd. And RESSPO Schedule.
- 4- Any loss & damage shall be recovered from the contractor account.
- 5- No T & P shall be supplied by the department at any cost. The transportation arrangement for safe carriage of materials shall be made by the Contractor. at his own risk.
- 6- All general conditions of contract for execution of work will be governed as per from 'A' (General conditions for the supply of plant and the execution of work in the U.P. Power Corporation Ltd.)
- 7- The work shall be carried out under the direct supervision of Junior Engineer and Sub-Divisional Officer concerned.
- 8- Department will not be responsible for any accident, casualties and loss occurred at the time of execution of work. The contractor shall be fully responsible for the same.
- 9- The necessary permit for shutdown etc. will be given to the contractor by the representative of the department as and when required for completion of work in a planned way.
- 10- The 90% payment shall be made on receipt bill against the works completed subject to availability of fund and remaining 10% will be detained as security which will be paid after 6 month from the date of completion of full work.
- 11- The Income Tax and other taxes will be deducted from the bill, if and as applicable.
- 12- Penalty @ ½% per week subject to maximum of 10% of the total value of the contract will be levied and deducted if the work is not completed within the stipulated period.
- 13- Service Tax shall be payable @ prevailing norms.
- 14- EE Concerned shall make the final payment after completion of work subject to availability of funds.

Executive Engineer
Electricity Distribution Division-I
Unnao